

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 25
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 7, 1871, under GLO contract No. 154, as follows:

Set a stone, 18" x 8" x 6", on southwest hillside for corner to sections 25, 30, 31 and 36.

T2S
R29E R30E
S25|S30
S36|S31
PLS 1636
2005

Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The original corner stone is 18" x 11" x 7" and is plainly marked with five notches across the top and the north edge.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 18" flared, galvanized iron pipe 15" into the ground to bedrock. I bury the corner stone along the northwest side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 30", attached at ground level, bears N36° 30' E, 164.4 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 31", attached at ground level, bears S57° 30' E, 136.3 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 36", attached at ground level, bears S23° W, 90.8 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 25", attached at ground level, bears N45° W, 201.4 feet.

This corner marks a point on the Morrow - Umatilla County line.

I hereby certify the above corner point was perpetuated as hereon described on February 10, 2005. Magnetic declination set in compass: 17° E.
NAD '83 UTM Zone 11 position: 5024828N, 331927E (plus or minus two meters).



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 2-05
Rec'd by KE
No. 05-33-R

V-1