


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 5
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 10, 1878, under GLO contract No. 293, as follows:

Set a stone, 20" x 10" x 7", on a bench for corner to sections 29, 30, 31 and 32. Dug pits and drove a willow stake as per instructions.



Original corner evidence recovered:

Found the original corner stone solidly set 12" into the ground. The corner stone is 21" x 11" x 6" and is plainly marked with five notches on the north edge and five notches on the east edge. The stake and pits of record are gone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 20" into the ground to bed rock. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 36" iron rod set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 29", attached at ground level, bears N18° E, 121.1 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 32", attached at ground level, bears S50° 30' E, 85.1 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 31", attached at ground level, bears S40° W, 161.4 feet.

A 5/8" x 36" iron rod set 31" into the ground with a 3/4" brass washer, marked "PLS 1636 30", attached at ground level, bears N42° 30' W, 87.5 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 10, 2002. Magnetic declination set in compass: 16° E.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**
Dennis L. Gaylord
**OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636**

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 2-02
Signed By KK
No. 02-36-R