

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 7
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 10, 1878, under GLO contract No. 293, as follows:

Set a stone, 15" x 10" x 8", on west hillside for the 1/4 section corner.

T2S R30E
1/4 S29
S32
PLS 1636
2002

Original corner evidence recovered:

Found the original corner stone firmly set on the west edge of a mound of stones. The corner stone is 16" x 11" x 7" and is plainly marked "1/4" on the north face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 22" into the ground. A 2 1/2" brass cap attached to the top of the iron pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N38° E, 200.3 feet.

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S43° E, 101.2 feet,

A 5/8" x 24" iron rod, set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S32° W, 94.4 feet.

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N53° W, 108.5 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 13, 2002. Magnetic declination set in compass: 16°E.


REGISTERED PROFESSIONAL LAND SURVEYOR
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636
Renews June 30, 2003

Recorded at the office of County surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 6-02
Rec'd By KE
No. 02-154-R