

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X - 17
DIAGRAM

History of original corner establishment:

The original corner was established by George S Pershin on September 4, 1878, under GLO contract No. 293, as follows:

Set stone, 18" x 10" x 6", for 1/4 section corner.

T2S R30E
1/4
S34|S35
PLS 1636
2002

Original corner evidence recovered:

Found the original corner stone solidly set 12" into the ground on the west edge of a mound of stones. The corner stone is 18" x 11" x 6" and is plainly marked "1/4" on the east face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 24" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the southwest side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N58° E, 94.5 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S32° E, 144.8 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S55° 30' W, 100.1 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N53° W, 94.8 feet.

I hereby certify the above corner point was perpetuated as hereon described on January 28, 2002. Magnetic declination set in compass: 18° E.



Dennis L. Gaylord



Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: _____

RECEIVED BY
 Umatilla County Surveyor
 Date 2-02
 Rec'd By KK
 No. 02-41-R