


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 5
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin, deputy, on October 20, 1871, under GLO contract No. 154, as follows:

Set a stone, 30" x 10" x 4", on west hillside for corner to sections 5, 6, 31 and 32.



Original corner evidence recovered:

Found the original corner stone solidly set but tipped to the northwest. The original corner stone is 28" x 11" x 4" and is plainly marked with five notches on the east edge.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 24" into the ground. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 32", attached at ground level, bears N47° 30' E, 79.8 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S5", attached at ground level, bears S40° 30' E, 115.4 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S6", attached at ground level, bears S36° W, 103.7 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 31", attached at ground level, bears N46° W, 101.7 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 15, 2005. Magnetic declination set in compass: 17° E.
NAD '83 UTM Zone 11 position: 5023158N, 333519E (plus or minus two meters).

Dennis L. Gaylord

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1836

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 2-05
Rec'd by KK
No. 05-48-R