


History of original corner establishment:

The original corner was established by David P. Thompson on October 6, 1864, under GLO contract No. 106, as follows:

Set stone 20" x 8" x 8" for 1/4 section corner.



Description of corner evidence found:

The original corner stone is solidly set 9" in the ground and plainly marked "1/4" on the north face. Stone measures 17" x 9" x 7" and is surrounded by a mound of stones.

Description of monument and accessories established to perpetuate the original location of this corner:

At the exact point occupied by the original corner stone, I set a 1 1/2" x 30" iron pipe, 25" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S36 NE", attached at ground level, bears N35°E, 62.0 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S1 SE", attached at ground level, bears S48°E, 56.4 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S1 SW", attached at ground level, bears S46°W, 58.0 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S36 NW", attached at ground level, bears N70°W, 66.4 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 2, 1997. Magnetic declination: 20°E.

REGISTERED PROFESSIONAL LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14 1978
DENNIS L. GAYLORD
1636

Renews 6/30/97

Office of COUNTY SURVEYOR County of UMATILLA
 State of OREGON, I hereby certify that the within instrument was filed in this office
 for record on the 11 day of March, 1997
David H. K... by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 3-97
 Rec'd by KK
 No. 97-39-R