

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The original corner was established by Daniel Chaplin on November 19, 1864, under GLO contract No. 107, as follows:

Set a stone 18" x 15" x 10" for corner to sections 2, 3, 10 and 11.

E - 17
DIAGRAM



Corner evidence recovered:

The original corner stone is loosely set in a mound of stones. The stone is 18" x 14" x 8" and is marked with one plainly visible notch.

Monument and accessories established to perpetuate the original location of this corner:

At the point occupied by the original corner stone, I set a 1" x 30" iron pipe, 12" into the ground to bedrock. I place the corner stone along the south side of the pipe and build a mound of stones around the pipe to the cap. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 NE", bears N47°E, 60.0 feet.

A 5/8" x 24" iron rod set 16" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 SE", bears S40°E, 42.8 feet.

A 5/8" x 24" iron rod set 20" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 SW", bears S73°W, 71.8 feet.

A 5/8" x 26" iron rod set 24" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 NW", bears N23°W, 75.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 21, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renew 6/30/1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 4-98
Rec'd By RK
No. 98-45-R