


History of original corner establishment:

The original corner was established by Daniel Chaplin on November 19, 1864, under GLO contract No. 107, as follows:

Set stone, 20" x 15" x 3", for 1/4 section corner.



Description of corner evidence found:

I found the original corner stone broken into several pieces. The pieces are in a mound of stones in a fence line projecting north and south. I reassemble the three largest pieces of the stone and find it measures 19" x 11" x 3". The top piece is plainly marked "1/4".



Description of monument and accessories I established to perpetuate the original location of this corner:

In the center of the stone mound I set a 1" x 30" iron pipe 26" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the pieces of the original corner stone around the pipe. The piece of stone marked "1/4" is buried along the north side of the pipe. I build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S11 NE", attached at ground level, bears N42°30'E, 102.8 feet.

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S14 SE", attached at ground level, bears S49°30'E, 104.8 feet.

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S14 SW", attached at ground level, bears S53°30'W, 140.2 feet.

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S11 NW", attached at ground level, bears N55°W, 68.0 feet.

I hereby certify the above corner point was perpetuated as hereon described on June 9, 1997. Magnetic declination: 20° E.

Office of Umatilla County County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 6 day of June, 1997
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor GPO-791-311
 Date 6-97
 Rec'd by KH
 No. 97-117-R