


History of original corner establishment:

The original corner was established by Daniel Chaplin on November 20, 1864, under GLO contract No. 107, as follows:

Set a stone 18" x 18" x 8" for the 1/4 section corner.



Description of corner evidence found:

The original corner stone is loosely set. The stone is 17" x 12" x 10" and is marked "1/4". There are no other stones in the vicinity of the corner.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**
Dennis L. Gaylord
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
 1636
Renews 6/30/99

Description of monument and accessories established to perpetuate the original location of this corner:

At the point occupied by the original corner stone, I set a 1" x 30" iron pipe, 26" into the ground. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe to the cap. A 2 1/2" brass cap attached is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod set 20" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 NE", bears N34°E, 81.3 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 SE", bears S16°E, 52.3 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 SW", bears S45°W, 74.1 feet.
- A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 NW", bears N31°W, 109.1 feet.

A fence corner with fences projecting northerly and southwesterly, and a very old down fence projecting southerly, bears N85°E, 114.4 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 3, 1998. Magnetic declination: 18°E.

Office of COUNTY SURVEYOR County of UMATILLA
 State of OREGON I hereby certify that the within instrument was filed in this office
 for record on the 5 day of March, 1998
David H. Klein by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor
 Date 3-98
 Rec'd By KK
 No. 98-24-R