


History of original corner establishment:

The original corner was established by Daniel Chaplin on November 20, 1864, under GLO contract No. 107, as follows:

Set stone, 20" x 6" x 6", for 1/4 section corner.



Description of corner evidence found:

The original corner stone is loosely set at the southwest edge of a large mound of stones. The stone is 24" x 6" x 6" and is plainly marked "1/4" on the north face.

Description of monument and accessories I established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in it's place a 1 1/2" x 30" iron pipe 14" into the ground to bedrock. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the southwest side of the pipe and build a mound of stones around the pipe to the cap, from which:

- A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S15 NE", attached at ground level, bears N48° E, 102.1 feet.
- A 5/8" x 24" iron rod, set 16" into the ground with a 3/4" brass washer, marked "PLS 1636 S22 SE", attached at ground level, bears S12° E, 89.4 feet.
- A 5/8" x 24" iron rod, set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 S22 SW", attached at ground level, bears S59° W, 189.3 feet.
- A 5/8" x 24" iron rod, set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 S15 NW", attached at ground level, bears N63° W, 93.5 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 14, 1997. Magnetic declination: 20° E.

Witnesses: Milena Gaylord  
Jacqueline Franco



Office of..... County of.....  
 State of..... I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
Umatilla County Surveyor

Date 4-97  
 Rec'd By KK  
 No. 97-65-R