


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 17

History of original corner establishment:

The original corner was established by Daniel Chaplin on November 19, 1864, under GLO contract No. 107, as follows:

Set a stone, 22" x 8" x 6", for the corner to sections 14, 15, 22 and 23.



Description of corner evidence found:

Found a stone broken into several pieces in a mound of stones. I reassemble the three largest pieces of the stone and find 3 notches on the edge of one piece and two notches on the edge of another piece. The reassembled stone measures 22" x 11" x 5".

Description of monument and accessories I established to perpetuate the original location of this corner:

In the center of the recovered mound of stones I set a 1 1/2" x 30" iron pipe 18" into the ground to bedrock. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the three corner stone pieces around the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S14", attached at ground level, bears N33° E, 113.6 feet.
- A 5/8" x 24" iron rod, set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 S23", attached at ground level, bears S55° E, 97.7 feet.
- A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S22", attached at ground level, bears S66° W, 121.9 feet.
- A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S15", attached at ground level, bears N29° 30' W, 110.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on May 12, 1997. Magnetic declination: 20° E.
Witness: Milena Gaylord.



Office of Umatilla County County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 17 day of May, 1997
Dennis L. Gaylord by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 5-97
 Rec'd By AK
 No. 97-102-R