


History of original corner establishment:

The original corner was established by Daniel Chaplin on November 19, 1864, under GLO contract No. 107, as follows:  
Set a stone 18" x 12" x 4" for the 1/4 section corner.



Description of corner evidence found:

The original corner stone is loosely set in an old fence corner. Fences project north and east. The stone is 18" x 11" x 5" and plainly marked "1/4".

Description of monument and accessories established to perpetuate the original location of this corner:

In the spot occupied by the original corner stone, I set a 1 1/2" x 30" iron pipe, 25" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S23 NE", attached at ground level, bears N31°E, 23.1 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S26 SE", attached at ground level, bears S25°E, 120.0 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S26 SW", attached at ground level, bears S11°W, 66.5 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S23 NW", attached at ground level, bears N31°W, 35.8 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 17, 1997. Magnetic declination: 20°E.

REGISTERED PROFESSIONAL LAND SURVEYOR

*Dennis L. Gaylord*

OREGON JULY 12, 1978 DENNIS L. GAYLORD 1636

Renews 6/30/97

Office of COUNTY SURVEYOR County of UMATILLA

State of OREGON, I hereby certify that the within instrument was filed in this office for record on the 17 day of February, 1997.

*David H. Klein*  
(COUNTY OFFICIAL)

by \_\_\_\_\_ (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 2-97

Rec'd By KK

No. 97-25-B