


History of original corner establishment:

The original corner was established by Daniel Chaplin on November 20, 1864, under GLO contract no. 107, as follows:

Set stone, 16" x 12" x 6", for 1/4 section corner.



Description of corner evidence found:

Found the original corner stone loosely set in a north-south fence line. The stone, which is 15" x 11" x 6", is plainly marked "1/4".



Description of monument and accessories I established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1 1/2" x 30" iron pipe 22" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the original corner stone along the southwest side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S28 NE", attached at ground level, bears N38°E, 141.9 feet.
- A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S28 SE", attached at ground level, bears S39°E, 108.5 feet.
- A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S29 SW", attached at ground level, bears S44°W, 104.2 feet.
- A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S29 NW", attached at ground level, bears N42°W, 141.2 feet.

I hereby certify the above corner point was perpetuated as hereon described on October 13, 1997. Magnetic declination: 20°E.

Office of _____ County of _____
 State of _____, I hereby certify that the within instrument was filed in this office
 for record on the _____ day of _____, 19____
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 10-97
 Rec'd By JK
 No. 97-194-R