


History of original corner establishment:

The original corner was established by Daniel Chaplin on November 18, 1864, under contract number 107, as follows:

Set stone 44" x 15" x 6" for the 1/4 section corner.



Description of corner evidence found:

Found a basalt stone, 39" x 16" x 6", plainly marked "1/4", lying on top of a mound of stones. Corner is about 50 feet east of a north-south barbed wire fence.

Description of monument and accessories established to perpetuate the original location of this corner:

In place of the corner stone, I set a 1 1/2" x 30" iron pipe 18" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I place the corner stone along the south side of the pipe and build a mound of stones around the pipe to the cap, from which:

A basalt rock outcrop, 10' wide x 5' high is marked "+36" on the southwest face 36" above the ground. The "+" bears N42°30'E, 37.2 feet. A 5/8" x 24" iron rod, set 22" into the ground with a 5/8" brass washer, marked "PLS 1636 S36", attached at ground level, bears S34°E, 63.6 feet. A 5/8" x 24" iron rod, set 24" into the ground with a 1 1/2" aluminum cap attached marked "PLS 1636 S35" with an arrow pointing toward the corner, bears S47°W, 42.2 feet. A 5/8" x 24" iron rod, set 22" into the ground with a 5/8" brass washer, marked "PLS 1636", attached at ground level, bears N41°W, 51.3 feet.

I hereby certify the above corner point was perpetuated as hereon descibed on November 11, 1996. Magnetic declination: 20°E.

**REGISTERED PROFESSIONAL LAND SURVEYOR**

*Dennis L. Gaylord*

**OREGON**  
JULY 14 1973  
**DENNIS L. GAYLORD**  
1636

Office of COUNTY SURVEYOR County of UMATILLA  
 State of OREGON, I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 \_\_\_\_\_ by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)

*RECORDED 6/30/97*

RECEIVED BY  
 Umatilla County Surveyor  
 Date 11-96  
 Rec'd By KK  
 No. 96-179-R