


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 13
DIAGRAM

History of original corner establishment:

The original corner was established by Daniel Chaplin on November 26, 1864, under GLO contract No. 107, as follows:



Set stone 17" x 9" x 8" for corner to sections 27, 28, 33 and 34.

On October 12, 1891, John C. Arnold, under GLO contract No. 551, was unable to find Chaplin's corner. Arnold set a basalt stone 14" x 8" x 5", 8" into the ground, marked with 3 notches on the east and one notch on the south face, in a mound of stones.

Corner evidence recovered:

Found Arnold's corner stone solidly set in a mound of stones. The corner stone is 15" x 8" x 4" and is plainly marked with 3 grooves on the east face and one groove on the narrow, south face. The corner is in a very old north-south fence line which is now only mounds of stones and down and decayed fence posts.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe, 15" into the ground to bedrock. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the north east side of the pipe and build a mound of stones around the pipe to the cap, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S27", attached at ground level, bears N18°E, 83.6 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S34", attached at ground level, bears S64°E, 49.9 feet.
- A 6" Ponderosa Pine scribed "T2S R32E S33 ET" on double blazes with a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "E", bears S00°30'W, 57.3 feet. This tree has a "Bearing Object" sign nailed above the blazes and a "Witness Post" sign nailed to the back.
- A 5/8" x 36" iron rod set 33" into the ground with a 3/4" brass washer, marked "PLS 1636 S28", attached at ground level, bears N70°30'W, 98.6 feet.

I hereby certify the above corner point was established as hereon described on September 3, 1999. Magnetic declination: 18°E.



Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on 12 October 1999.

RECEIVED BY
 Umatilla County Surveyor
 Date 10-99
 Rec'd By KK
 No. 99-211-R