


USDA-FOREST SERVICE

Index File No. Z-21
 T 2S R. 32E
 Merid. WILLAMETTE

CORNER RECORD (SEARCH)
 (Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____
 R.D. NORTH FORK J.D. County UMATILLA
 N.F. UMATILLA State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a stone 19x12x10 inches with possible marks loose on the ground approximately 4 feet Northwest of corner position.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 38 inch diameter Ponderosa Pine bears N45°E, 30 lks, live but sickly with scribes visible.
 A 24 inch diameter Ponderosa Pine stump bears N17°W, 63 lks with bottom of blaze evident.

PHOTO IDENTIFICATION DATA
 1687-162

Photo No. _____
 Filed At. Ranger Office
 Object Ident. As shown
 Ident. By D.I. Griffith
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on timbered flat approximately 8 feet South of an East-West fenceline and approximately 450 feet Northwesterly of the 300 road.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____

Agency
 Signature _____

Title SURVEYOR Division _____ Headquarters _____

Date 9-7-88 FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2½"x30" aluminum pipe with aluminum cap marked as shown:
Pipe is set 30 inches in the ground.

T2S R32E
S 35 | S 36

Buried the original corner stone North and alongside of monument.

S 6
T3S R33E
1988
OPLS 644

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New BTs:

A 11 inch diameter Western Larch bears N30°E, 65.34 feet marked T2S R32E S36 BT

A 9 inch diameter Douglas Fir bears N60°W, 19.81 feet marked T2S R32E S35 BT

Painted a 6 inch red band around all bearing trees and attached 54-3 and 54-9 signs.

Set a steel fencepost approximately 5 feet East with 54-9 and 54-2 signs attached.

Work Done By D.I. Griffith Title Surveyor Date 8-20-88 State Registration No. OPLS 644
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Umatilla County Surveyor Office Date 10-88

REMARKS

Index File No. Z-21

T. 2S

R. 32E


WM.

Tract or Surv. No.

Cor.

Index File No. Z-21 CORNER RECORD (SEARCH) (Ref. FSM 7151.4) Tract or Survey No. _____ Cor. No. Z-21
 T 2 S R. 32 E R.D. Ukiah County Umatilla
 Merid. Willamette N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Material: Stone
 Size: Approximately fits GLO
 Markings: None visible. If this is the proper stone, it is about 6 to 8 ft. west of location which fits B.T.'s. 2

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 40-inch pond. pine bears N 45°E approximately 20 ft. It has been cut out to an old blaze. I cannot read scribing, but old blaze has been burned. Tree has B.T. tag, Attention poster and Forest boundary poster. A 30-inch pond. pine stump bears N 17°W. approx. 40 feet. It appears to have old low blaze and I placed a blank B.T. tag on it. 3

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
Signature 7

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

There is an east-west fence approx. 12 feet north of corner's assumed location. 4

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
Agency 8

Land has been logged north of fence.

Signature
 Tom Hollamon

Title
 eng. tech.

Division

Headquarters

Date
 11/19/75

7100-52 (3/68)

5

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

9

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

10

Work Done By _____ Title _____ Date _____ State Registration No. or Agency _____

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

REMARKS

Original GLO notes say it is corner to sections 1, 2, 34 and 35. It must have been 1, 2, 35 and 36 at that time. It is now common to only 35 and 36, T.2S., R.32E. However, I have no notes for the retracement.

12