


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by David P. Thompson under GLO contract number 106, dated August 16, 1864. Surveyor General record states:

Set stone 20x8x6 in for 1/4 sec corner



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found stone 17x8x5 inches with chiseled 4 visible, in a rock jack approximately 120 feet Southeast of the proportioned position for the corner.

See survey dated September, 1988.

Description of monument and accessories established to perpetuate the original location of this corner: At position determined by survey, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 15 inches in the ground, from which:

New Bearing objects;

A 5/8"x24" copper clad iron pin with plastic cap marked BGA SURVEY MARKER bears N42°E, 11.45 feet.


A 5/8"x24" copper clad iron pin with plastic cap marked BGA SURVEY MARKER bears N49°W, 10.84 feet.

Raised a mound of stone around monument, 4 ft. base to top of cap. Placed original stone under the West side of the mound.

Set a steel fencepost approximately 5 feet East with land survey monument sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on September 1, 1988.

Witnesses: Jeff Petersen and Rick Robinson



REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 10, 1964
DUANE I. GRIFFITH
644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination.

Office of... Survey County of... Umatilla
State of... OR I hereby certify that the within instrument was filed in this office
for record on the... 27th day of... September... 19... 88
... David H. Lumbria... by Kathleen X. Ambrey
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 8-88

Rec'd By KA

No. 88-92-c

☆ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

Z-23