


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. X-(1-3)

History of original corner establishment:

No original corner was set.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2½"x30" Galvanized Pipe with brass cap stamped:

Set pipe 26" in ground with mound of stone to cap.

Bearing Trees:


A White Fir 10" dia. bears S62°E, 30.5 ft., scribed 1/4 S 31 BT.

A White Fir 12" dia. bears N52°E, 39.8 ft., scribed 1/4 S31 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.

Attached 54-4 sign to Polymer post with 54-2a sign attached.

T2S  
R32E | 1/4 | R33E  
| S31  
1980  
OR PLS 1294



I hereby certify the above corner monument was established as herein described on October 23, 1980.

Witnesses: R. Orton  
G. Wagoner  
M. Wyatt

Office of..... County Surveyor..... County of..... Umatilla  
State of..... Oregon..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of..... December....., 1980  
David Krummen..... by Betty Shatto.....  
(COUNTY OFFICIAL) (DEPUTY)

R-188-B