

USDA-FOREST SERVICE

Index

File No. X-(1-3)

T 2S R. 33E

Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. \_\_\_\_\_

Cor.

No. 1/4

R.D. Ukiah

County


Umatilla

N.F. Umatilla

State

Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None was originally set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on fairly steep south slope approximately 150 ft. north of bottom of E-W draw.

*Signature*  
*Howell & Sons*

Title

Division  
ORLS

Headquarters  
1294

Date  
9/77

7100-52 (3. 68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

At surveyed point set 2½"x30" Galvanized Pipe with brass cap stamped:

T2S  
R32E | 1/4 | R33E  
      | S31  
      1980  
      OR PLS 1294

Set pipe 26" in ground with mound of stone to cap.

**ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

Bearing Trees: A White Fir 10" dia. bears S62°E, 30.5 ft., scribed 1/4 S31 BT. A White Fir 12" Dia. bears N52°E, 39.8 ft., scribed 1/4 S31 BT. Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs. red. Attached 54-4 sign to Polymar post with 54-2a sign attached.

Work Done By R. C. Orton Title Party Chief Date 10/23/80 State Registration No. or Agency \_\_\_\_\_

Certified Cor. Record Prepared ? Yes  No \_\_\_\_\_ Filed At: \_\_\_\_\_ Date \_\_\_\_\_

Witnesses: R. Orton  
              G. Wagoner  
              M. Wyatt

REMARKS

Index File No.      T.      R.      M.      Tract or Surv. No.      Cor.      12

X - 1      25      33E                     13