

USDA-FOREST SERVICE

Index File No. X-1
 T 2S R. 33E
 Merid. Willamette

CORNER RECORD (SEARCH)


(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla
 N.F. Umatilla State Oregon

Tract or Survey No. _____

Cor. C 1 / 16 - 80
 No. _____

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

No corner was originally set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
 Signature _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on a steep east slope in Pine and Fir timber around 200' west of a Jeep Road.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
 Agency _____


Signature *[Handwritten Signature]*

Title _____ Division ORLS Headquarters 1294 Date 9-77
 7100-52-(3-68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2 1/2" x 30" galvanized pipe with brass cap stamped:



Set pipe 20" in ground with mound of stone to cap.

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Bearing Trees:

A Douglas Fir 11" dia. bears S17°E 27.8 ft, scribed C 1/16 80 S31 BT.

A Ponderosa Pine 10" dia. bears N83°E 28.3 ft, scribed C 1/6 80 S31 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washer stamped LS1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's Red.

Attached 54-2 & 54-4 signs to metal post 5' east of corner. Attached 54-2 and 54-9 signs to metal post 5' south of corner.

Work Done By R. C. Orton Title Party Chief Date 8-21-80 State Registration No. or Agency

Certified Cor. Record Prepared? (Yes) No Filed At: _____ Date _____

Witnesses: R. Orton
G. Wagoner
G. Lester
J. Anderson

REMARKS

Index File No. T. R. M. Tract or Surv. No. Cor.

X-180 29 33E