


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. X-3

History of original corner establishment:  
No corner was originally set.




Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2"x30" galvanized pipe with brass cap stamped:

Set pipe 15" in ground with mound of stone to cap.



Bearing Trees:

A Douglas Fir 12" in dia. bears N18°E 7.0 ft, scribed C 1/4 S31 BT.

A Douglas Fir 11" in dia. bears S74°E 12.5 ft, scribed C 1/4 S31 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washer stamped LS1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's Red. Attached 54-2 & 54-4 signs to metal post 5' south of corner. Attached 54-2 & 54-9 signs to metal post 5' west of corner.

I hereby certify the above corner monument was established as herein described on August 21, 1980.

Witnesses: R. Orton  
G. Wagoner  
G. Lester  
J. Anderson



Office of..... County Surveyor..... County of..... Umatilla  
Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of..... December....., 1980  
..... by.....  
(COUNTY OFFICIAL) (DEPUTY)

R-188-B