


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX FILE NO. Z-1

History of original corner establishment:
No corner was originally set.



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2"x30" galvanized pipe with brass cap stamped:
Set pipe 20" in ground with mound of stone to cap.

T2S	R33E
$\frac{1}{16}$	S31 80
T3S	
1980	
OR PLS 1294	


Bearing Trees:

A Douglas Fir 9" dia bears N17°E, 8.6 ft, scribed 1/16 S31-80 BT.
A Douglas Fir 9" dia. bears N57°W, 19.7 ft, scribed 1/16 S31-80 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washer stamped LS1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's Red. Attached 54-2 & 54-4 signs to metal post 6' north of corner. Attached 54-2 & 54-9 signs to metal post 6' west of corner.

I hereby certify the above corner monument was established as herein described on August 25, 1980.

Witnesses: R. Orton
G. Wagoner
G. Lester
J. Anderson



Office of..... County Surveyor..... County of..... Umatilla
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... December....., 19..... 80
 David Brumbern..... by..... Betty Shatto.....
 (COUNTY OFFICIAL)..... (DEPUTY)