

Index File No. Z-13

CORNER RECORD (SEARCH)


Tract or Survey No. _____

Cor. ~~80~~ 8
No. Z-13

T 25 R. 33E
Merid. WILLAMETTE

R.D. UKIAH County Umatilla
N.F. UMATILA State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

10' DBH FIR BT BEARING S2°E 105 LKS TREE GREEN AND STANDING
CHOPPING REVEALED SCRIBING
30' DBH FIR, BEARING N50°E, 214 LKS - DEAD AND FALLEN
IN ADVANCED STATE OF DECAY. BLAZE ON UNDERNEATH
SIDE OF TREE.
EVIDENCE OF A TUMBLED DOWN MOUND AT CORNER

PHOTO IDENTIFICATION DATA

Photo No. E90 9/3/66
8-237
Filed At. _____

Object Ident. SUB-PT
Ident. By Tom Sullivan
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

CHAINED (E) FROM NW COR. OF SEC 1, T35 R33E
CORNER IS 1 CHAIN SOUTH OF THE BOUNDARY FENCE
IN A CLEARING ON AN EAST FACING SLOPE.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature: Mike Lilly

Title ENG-AID

Division USFS

Headquarters UMATILA S.D.

Date 8/7/69

7100-52
REV. 65 5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

NONE

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

PAINTED BT'S RED AND FLAGGED FENCE
PLACED BT SIGNS (54-3) ON BT'S
PLACED ATTENTION SIGN (54-4) ON 10" BT

Work Done By. T.E. SUTHERLAND Title ENG AID Date 8/7/69 State Registration No. US FOREST SERVICE
or Agency

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

THERE IS A WELL PRESERVED MOUND IN THE AREA BUT IT IS NOT THE PROPER DISTANCE OR BEARING
PIN-PRICKED A 6" DBH FIR BEARING S81W, 106 LKS FROM 10" FIR BT WHICH BEARS S2°E, 105 LKS FROM COR.

Index File No. Z-13 T. 2S R. 33E M. WILL Tract or Surv. No. _____

Cor. Z-13