

Index

File No. MP67

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. M.P.

T 2S R. 34E

R.D. La Grande


County Union

Merid. Willamette

N.F. Wallowa-Whitman

State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found 2" iron pipe with brass cap marked.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Barry B. Barber
Signature Title P, L, S.

Division

Headquarters

Sumpter

Date

11-6-80

7100-52 (3. 68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Found 2" iron pipe with brass cap marked; Cap straight but loose, T2S R34E
Firmed up with 6x36 inch mound of earth and mound of stone UIR
around to cap. Cap 20" above ground. 67M
1917

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which by magnetic declination of N20°E: A down and rotten pine bears N45°E, 56.6 ft. A 24" fir bears N62°E, 78.1 ft with grown over blazes. A 40" fir bears S61°E, 15.4 ft. with grown over blazes. Painted 6" red bands around. Two good BTs. Placed 54-3s, and 54-4s Placed 54-2 and 54-4 on steel fence post 5' east of the corner. No trace of 20" fir, N23°W, 58 links.

Work Done By B. B. Barbour Title P.L.S. Date 11-6-80 State Registration No. OR 1051
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Union County Surveyor's Date

REMARKS

Witnesses: Daniel Rowland
Doug Moser
Ron Gilroy