

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 10/11/01

CORNER DESIGNATION: Z-25, Township 1 South, Range 35 East, Section 36.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner originally established by John A. Hurlburt under Contract No. 201, dated August 5, 1873. Notes state: Set pine post 5ft long 5in square 2ft in ground, from which:

- A 12" Fir bears N 64° W, 24 lks.
- A 8" Pine bears S 17° W, 21 lks.
- A 8" Pine bears N 23° E, 35 lks.
- A 10" Pine bears S 65° E, 14 lks.

Union County Survey 11-82, by StateParks Dept. reestablished corner by survey and calls:

Section corner falls in an 11" Tamarack. Put corner tag on this tree and scribed as follows:

- On NW face "T1S R35E S36"
- On NE face "T1S R36E S31"
- On SE face "T2S R36E S6"
- On SW face "T2S R35E S1", from which:

19" fir S17°W, 19.2' to center, scribed "T2S R35E S1 BT".

17" fir S60°E, 25.1' to center, scribed "T2S R36E S6 BT".

12" tamarack N75°E, 16.9' to center, scribed "T1S R36E S31 BT RS691".

11" tamarack N65°W, 8.8' to center, scribed "T1S R35E S36 BT".

Corner maintained by G. Blackman, PLS 991, in November 1995, File No. 030-1995R. Record states: Found

11" Tamarack blazed and scribed as per 11-82. Found 18" white Fir snag bears S16°W, 19.65 feet blazed and scribed. Found 11" Tamarack bearing N66°W, 8.61 feet, blazed and scribed, alive and vigorous.

New bearing trees set:

A 13" Tamarack bears N84°E, 33.40 feet, marked T1S R36E S31 BT.

A 9" Lodgepole Pine bears South, 6.10 feet, marked T2S R36E S6 BT.

A 14" Tamarack bears S74°W, 26.61 feet, marked T2S R35E S1 BT.

**MONUMENT AND ACCESSORIES FOUND:**

Found 12" tamarack corner tree marked by State Parks, from which:

A cut 12" tamarack stump, bears N 75° E, 25.1', partial visible scribes, (State Parks BT)..

A dead, fallen 17" fir, bears S 60° E, 25.1', (State Parks BT).

A dead 19" fir, bears S 16° W, 19.65', (State Parks BT).

A dead 11" tamarack, bears N 66° W, 8.61', (State Parks BT).

A 14" tamarack bears N 84° E, 33.40 feet, (Blackman BT).

A dead 8" lodgepole pine bears South, 6.10 feet, (Blackman BT).

A dead 16" tamarack bears S 74° W, 26.61 feet, (Blackman BT).

**MONUMENT MARKING DETAIL:**

T1S  
R35E|R36E  
S36 | S31  
S1 | S6  
T2S

New accessories:

A 8" lodgepole pine bears S 26° E, 55.4 feet, scribed "T2S R36E S6 BT".

A 20" western larch bears S 82° W, 50.2 feet, scribed "T2S R35E S1 BT".

A 14" western larch bears N 39° W, 55.3 feet, scribed "T1S R35E S36 BT".

Attached bearing object signs to new bearing trees. Attached witness post sign to corner tree.

Nailed brass washer stamped "PLS 1106" nailed to "B" of "BT" on all new trees.

**LOCATION AND COMMENTS:**

**STATE PLANE CO-ORDINATE:**

Oregon North, NAD 83/91, International Foot:

N= 649727.7

E=8749806.5

FIRM: William R. Wells, PLS

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

Mark Hammersla

1S35Z25

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

RECEIVED BY  
Umatilla County Surveyor  
Date 11-01  
Rec'd By RK  
No. 01-128-R