


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

This corner was established by James E. Noland on June 22, 1887, under special contract as follows: A basalt stone in place 5' x 5' x 3' above the ground marked 59M on the north, UR on the west and + on the top at the exact corner point, from which: A 16" pine bears S25°E, 69 links (45.54 feet). This corner supersedes the corner set by Moody in 1871. On October 30, 1917, L. E. Wilkes perpetuated this corner under Group number 29 as follows:

A boulder 4' x 3' x 3' above the ground marked UR on the west face (very dim) and other marks illegible, from which a 24" pine, marked "59M UR" with a healed lower blaze, bears S20°E, 70 links (46.2 feet). Wilkes cut a cross on top of the boulder and UR 59M on the west face and a new bearing tree: A 4" pine marked "UR59M BT" bears S42°E, 18 links (11.88 feet).



Description of corner evidence found:

I find the original corner, a boulder 54" x 54" x 48" above the ground. I find a "+" on the highest tip of the boulder and "UR" deeply chiseled on the west face. The bearing trees of record are gone. This boulder is the northerly of a group of boulders and is about 6' east of a wire fence which generally follows the Reservation boundary.

Description of monument and accessories I established to perpetuate the original location of this corner:

To reference this corner, I set a 5/8" x 24" iron rod, 23" into the ground with a 1 1/2" aluminum cap attached which is marked as shown in the diagram above. I set this monument S21° 02'W, 52.1 feet from the "+" on the boulder (at record bearing between 59M and 59 1/2M). I drive a 6' steel fence post S21°W, 0.3' from this monument. From the "+" on the boulder:

- A 17" Ponderosa Pine, marked "UIR 59M BT", bears N79°E, 83.5 feet.
- A 19" Ponderosa Pine, marked "UIR 59M BT", bears N35°W, 127.6 feet.

Both new bearing trees are scribed on double blazes, have a bearing tree sign nailed above the blazes and have a 5/8" brass washer, marked "PLS 1636", nailed flush to the lower blaze.

I hereby certify the above corner point was perpetuated as hereon described on October 29, 1995. Magnetic declination: 20°E.



Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 11-95
Rec'd By KK
No. 95-194-R