

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-1
P-25

History of original corner establishment:

This corner was originally established by Jacob Cooper under G.L.O. contract no. 397 dated July 1, 1881. He set a wood post 3' long and 3" square 18" in the ground.

From which:

- A Pine, 18" dia., N73°E, 83 lks.
- A Pine, 12" dia., N81°W, 165 lks.

Corner was found by L.E. Wilkes, U.S. Surveyor, during his re-survey in 1917. He found only the two original BTs. At record bearing and distance he set a 1" by 3' iron pipe with a brass cap marked:


From which the original BTs:

- A Pine, 20" dia., N73° 30'E, 83 lks.
- A Pine, 20" dia., N81° 30'W, 164 lks.


He built a mound of stone around the corner monument.

Description of corner evidence found:

Found a stone mound with the corner monument as described by Wilkes lying alongside and two pine BTs.



P-25



Description of monument and accessories I established to perpetuate the original location of this corner:

Replace Wilkes corner monument in stone mound. (Note: Record distances do not fit either stone mound or record bearings).

From the corner, the original BTs:

- A P. Pine stump, 27" dia., N70°E, 54.7 ft with scribing visible.
- A P. Pine, 32" dia., N78 1/2°W, 110.6 ft. with a mostly healed blaze.

A new BT:

A P. Pine, 7" dia., E., 24.5 ft. marked: 1/4 S19 BT

Bts have blaze and a 6" stripe painted red, a BT tag and an "Attention" sign. New BT has, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with an "Attention" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 19 1/2°E.

September 3, 1984.

REGISTERED PROFESSIONAL LAND SURVEYOR

Fayette S. Munro

OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 10 day of October, 1984
David H. Krumboltz by [Signature]
 (COUNTY OFFICIAL) (DEPUTY)