


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-146
34
14

History of original corner establishment: Corner established in 1874 by John A. Nurburt under General Land Office Contract No. 201.

Surveyor General Records (notes) states:

- Set a pine post 4 ft. long, 4 in. square, 2 ft. in ground for cor to Sec 1-2-36
- Fir 2 1/4 in. dia. N55°W 99 lks.
- Pine 8 in. dia. S33°W 42 lks.
- Tamarack 15 in. dia. S34°E 83 lks.
- Pine 10 in. dia. N63°E 43 lks.



Z-21

(No subsequent remonumentations in county records)

Description of corner evidence found:

Found 4 in. x 4 in. post, rotted off 1 ft. above the ground with marks visible, surrounded by a mound of stone, all appear to be original.

Found pine stump, badly rotted, no marks visible, bearing N63°E, 27 ft. dist.

Found 30 in. tamarack, living in good condition, marks clearly visible, bearing S34°E, 55 ft. dist.

Found down and rotten pine with marks visible bearing S33°W, 28 ft. dist.


Found remains of rotten fir stump with blaze preserved and marks visible bearing N55°W, 67 ft.

Description of monument and accessories established to perpetuate the original location of this corner

At the position of the 4 in. x 4 in. post in mound of stone, set 30 in. x 2 1/2 in. iron pipe with 3 in. brass cap marked as shown, 30 in. in the ground and placed stones around pipe for the corners to Sec. 35, 36, 1 and 2.

From which new BT's

- A 6 in. fir bears N45°E, 35.8 ft. dist. marked T1S, R36E, S36 BT.
- A 18 in. fir bears S35°W, 31.0 ft. dist. marked T2S, R36E, S2 BT.
- A 10 in. fir bears N40°W, 13.5 ft. dist. marked T1S, R36E, S35 BT.



All distances taken to a brass washer in the blaze of each tree.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Douglas M. Ferguson
OREGON
JULY 12, 1951
DOUGLAS M. FERGUSON
848

Set a steel fence post approximately 5 ft. West of pipe with Forest boundary sign attached.

Used steel tape and magnetic compass with declination = 20°E.

Office of Surveyor County of Wasco
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 16 day of April, 1972, at 11 o'clock A.M., (signed)
Douglas M. Ferguson by _____ (DEPUTY)
(COUNTY OFFICIAL)

H-146