

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/22/23.

CORNER DESIGNATION: E-1, the Southwest Corner of Section 6, Township 3 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by N.H. Gates under Contract No. 84, dated July 22, 1859. Gates set a post in earth mound. A locally accepted and recognized fence corner with fences South and West was accepted for the corner point and monumented by Otis Gould, U.S Department of the Interior Surveyor in 1940. Gould monumented with a 2" by 3' long iron post with brass cap. Gould reference the brass cap monument with dug pits 18"X18"X12", 3' distance from the monument in each section. On Survey No. 90-49-B, the monument was recovered and referenced with brass capped witness corner monuments North and West A condition report recorded as 02-282-G, (illegible), recovered the corner. The corner monument and the Northerly witness corner monument were recovered on Survey No. 13-015-C.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on 2" iron pipe buried 28" in a farmed irrigation circle. The North witness monument per Survey No. 90-49-B was also recovered. The corner monument cap is stamped as shown in Monument Marking Detail.

MONUMENT MARKING DETAIL:

T3N
R27E | R28E
S1 | S6

S12 | S7
1940

MAINTAINED CORNER MONUMENT:

From the corner monument:

A 2 1/2" brass cap on galv. iron pipe witness monument bears N 00°40'11" W, 424.98'. Set a 3' tall wood post on East side of witness monument and a new steel fence post 6" North of witness monument with a witness post and bearing object signs attached.

New accessories:

A Pink Deep-1 magnet bears S 50°42'36" E 34.33' buried 28" with bearing object sign.
A Blue Deep-1 magnet bears S 27°20'58" W 31.25' buried 28" with bearing object sign.
An Orange Deep-1 magnet bears N 41°16'12" W 33.33' buried 28" with bearing object sign.

Courses to corner accessories are State Plane Grid bearings and distances.

LOCATION AND COMMENTS: The corner falls in a farmed irrigation circle.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 766276.66
E: 8489829.44

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\3N28E-1



RENEWS: 6.30.24

24-004-C