

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/27/23.

CORNER DESIGNATION: E-21, the Northeast corner of Section 11, Township 3 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by N.H. Gates under Contract No. 84, dated July 22, 1859. The corner was reestablished on Survey No. 253, found in Record of Private Survey Books. A "marked stone" was set for the corner on that survey. The corner was also called on Survey No. 258, found in Record of Private Surveys. Survey No. 258 does not call the monument found.

MONUMENT AND ACCESSORIES FOUND: None. Held the intersection of Emert Road centerline East-West and a fence Line extending North and South as Best remaining evidence of corner.

MONUMENT MARKING DETAIL:

T3N R28E
S2 | S1

S11 | S12
2023
PLS 54657

NEW MONUMENT SET:

At the intersection described above, set a 2 1/2" brass cap on 1 1/4" galvanized iron pipe with brass cap 12" below the road surface. The brass cap is marked as shown in the Monument Marking Detail.

New accessories:

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 49°15'09" E, 53.20', in East-West fence line, 6" Southwest of a 4" wood fence post. Nailed bearing object signs to wood post.

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S61°21'37" E, 64.62', In East-West fence 6" North of wood post. Nailed bearing object sign to wood post.

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 00°19'41" W, 31.61', 12" North of railroad tie fence corner post with fences East-West and South. Nailed Witness post and bearing object sign to the railroad tie post.

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears N 39°37'48" W, 40.35', 8" South of a 6" metal post in East-West fence line. Wired bearing object sign to rebar near the metal post.

Courses to corner accessories are State Plane Grid bearings and distances.

LOCATION AND COMMENTS: The corner monument is located in Emert Road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 766384.94
E: 8516186.91

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\3N28E-21



RENEWS: 6!30!24

24-004-C