

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 04/06/23.

CORNER DESIGNATION: N-2, the West 1/16th corner common to Sections 18 & 19, Township 3 North, Range 28 East, W.M., was maintained as a reference to Corner N-3, the South Quarter corner of Section 18, which falls in a large irrigated circle.

PREVIOUS RENEWALS/SURVEYS ETC: Corner N-3, the South Quarter corner of Section 18, was originally established by N.H. Gates under Contract No. 84, dated July 22, 1859. Gates set a post in earth mound. Survey No. 198, in 1904, recorded in Record of Private Survey Books, declared the corner lost and reestablished and monumented with a "stake in machine wheel". Corner N-3 was computed on Survey No. 00-33-B but not monumented.

MONUMENT AND ACCESSORIES FOUND: Corner N-3 was computed but not monumented as is falls in a large irrigated circle. The monument for the existing West 1/16th corner common to Sections 18 & 19 was maintained as a reference to Corner N-3 as described below.

MAINTAINED CORNER DESIGNATION:

T3N R28E  
S18  
W 1/16 -----  
S19

MAINTAINED MONUMENT:

Found a 5/8" rebar with red plastic cap as established on Survey No. 00-33-B, with plastic cap set flush with ground in a North-South fence line. Attached witness post sign to steel fence post 4' South of monument.

New Accessories:

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS bears N 01°37'59" W, 67.70', set 4" West of wood fence post in North-South fence line. Nailed bearing object sign to wood fence post.

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS bears N 01°43'17" W, 30.01', set in a North-South fence line. Wired bearing object sign to rebar.

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS bears S 00°23'03" E, 25.15', set in a North-South fence line. Wired bearing object sign to the rebar.

A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS bears S 00°18'11" E, 67.81', set 4" West of wood fence post in North-South fence line. Nailed bearing object sign to wood fence post.

Courses to corner accessories are Oregon State Plane Grid bearings and distances.

LOCATION AND COMMENTS: The maintained corner monument is located West of a large irrigated circle.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 755663.79

E: 8491177.11

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\3N28N-2



RENEWS: 6.30.24

24-004-C