

**OREGON CORNER RESTORATION FORM**

Section 20,21 Township 3N  
County Umatilla Date: 03/05/10

Range 29E

Corner Designation: 3N29P9

Corner common to Sections 20,21, T3NR29E.


- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out

**Previous Renewals / Surveys, etc.**

Originally Surveyed by Gates. He set a post in a mound of earth in 1859.

**Monuments and Accessories Found: (Condition and Source)**

None. This whole area has been regraded, and smoothed, for center pivots.



Edge of Circles

Sketch

Magnets are app.  
1.6' deep.

2 1/2" BC

NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N753468.72  
E8532855.39

LAT - 45° 43' 33.8609752" N  
LON - 119° 12' 17.26914421" W

**Monument (s) Set (Procedures and Description)**

A 2 1/2" Brass cap on a 1" id x 30" galvanized Iron pipe, buried 23" below surface. Cap marked as shown above.

**References Set:** "Deep One" magnets by Berntsen.

- An Orange magnet, 19" deep, lies N 43°30' W, 18.69'.
- A Silver magnet, 19" deep, lies N 45°20' E, 14.55'.
- A Pink magnet, 19" deep, lies S 28°50' E, 22.35'.
- A Blue magnet, 18" deep, lies S 47°45' W, 19.96'.

**Location and Comments**

The corner is 1.2 miles South of the intersection of Hwy 320. and Snow Road and .5 miles East .

**Compass Declination**

17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
 OREGON  
 JANUARY 11, 2005  
 ROBERT DOUGLAS ENGLISH  
 43406LS

RECEIVED BY:

Date: 3-10  
 Rec'd By: KE  
 No. 10.35-A

**Firm / Agency**

Survey One, LLC.  
 P.O. Box 382  
 Pendleton, OR 97801  
 (541) 276-2055

RENEWAL DATE: 12/31/11