

OREGON CORNER RESTORATION FORM

Section 29,30 Township 3N
County Umatilla Date: 03/08/10

Range 29E

Corner Designation: 3N29T5

1/4 Corner common to sections 29,30 T3NR29E

Condition Report Only
 Not Found
 Remonumented
 Unrecorded
 Surveyed In
 Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by Gates, set a post in a mound of earth, 1859.
Harris set a 1/2" Iron rebar in survey #Q-1655.


Monuments and Accessories Found: (Condition and Source)

None.

Diagram



Sketch



NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N748049.68
E8527655.84

LAT - 45° 42' 41.18664" N
LON - 119° 13' 31.76774" W

Monument (s) Set (Procedures and Description)

Set a 1 1/4" x 30" galvanized iron pipe with a 2 1/2" brass cap, 22" below surface, stamped as shown above. Set by single proportion between found monuments North and South one half mile.

References Set: "Deep One" magnets by Berntsen.

- A Silver magnet, 18" deep lies N 45°40' E, 16.34'.
- A Pink magnet, 18" deep lies S 16°20' E, 17.19'.
- A 5/8" x 30" Iron rebar w/rpc# 43406 lies S 63°50' W, 20.44'.
- A 5/8" x 30" Iron rebar w/rpc #43406 lies N 81° W, 18.99'.

Location and Comments

The corner is 1.5 miles South of the intersection of Hwy. 320 and Whitehouse Road, then East on a gravel road 1.0 mile.

Compass Declination
17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 1-11
Rec'd By: KK
No. 11-18-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11