

OREGON CORNER RESTORATION FORM

SECTION: 3 TOWNSHIP: 2N RANGE: 29E A-13

COUNTY: UMATILLA DATE: 8/2010

CORNER DESIGNATION

NW 3

 CONDITION REPORT ONLY
 NOT FOUND
 X *RENEWED*
 UNRECORDED
 SURVEYED IN
 X *REFERENCED OUT*

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Thompson under Contract #83 in 1859. He set post and made mound. In 1962 Wayne Harris Set a 3" iron pipe in a survey for Pendleton ranch-Cunha ranch.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

2' south of fence corner, found 3" iron pipe with a 6"x 9" iron plate welded to the top.

MONUMENT DETAIL

T3N R29E
33 | 34
4 | 3
T2N

OREGON STATE PLANE COORDINATES NORTH ZONE, NAD 83(91), Int Feet:

740313.96
8538382.40

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 20° 46' 41" E 37.86'
A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 87° 44' 53" E 48.13'
A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 2° 08' 33" E 33.90'
A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 15° 26' 24" W 99.49'
These bearings and distances are State Plane.

LOCATION AND COMMENTS

From the intersection of the Heppner to Echo Highway with Snow Road go South on Snow Road 4.1 miles to a fence line. Go East along fence line 1.5 mile to fence corner. Go north along fence 1 mile to corner.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: G. EDWARDS
WITNESS: R. SMITH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/11