

CORNER RESTORATION FORM

Township 3N Range 30E Section 11 & 12 County UMATILLA

State OREGON Date 4-10-2015 Number G-21

Corner Designation : 1/4 CORNER SECTION 11 & 12

Previous Renewals ORIGINAL SOURCE OF CORNER

UNDER GLO CONTRACT #81 BY D. THOMPSON DATED
JULY 8, 1859 SET POST

Accessories Found:

NONE


BASIS OF BEARINGS, NAD 83/91 OREGON STATE PLANE COORDINATES NORTH ZONE:

NORTHING: 764928.464
 EASTING: 8580838.697

- Condition Report Only
- Not Found
- Renewed
- Surveyed In
- Referenced

MONUMENT DETAIL

Found Set



Monument & Accessories Set (Procedure and Description)

- SET 2 1/2" BRASS CAP ON 1 1/2" PIPE 1' BELOW GRADE. SET SURVEY MARKER SIGN ON GREEN STEEL POST.
- SET 5/8" REBAR & CAP PLS 61420 1' BELOW GRADE, N56°07'E 37.57'. SET BEARING OBJECT SIGN ON GREEN STEEL POST.
- SET 5/8" REBAR & CAP PLS 61420 1' BELOW GRADE, S61°35'E 50.51'.
- SET 5/8" REBAR & CAP PLS 61420 2' BELOW GRADE, S50°40'W 27.14'.
- SET 5/8" REBAR & CAP PLS 61420 1' BELOW GRADE, N66°04'W 28.88', SET BEARING OBJECT SIGN ON GREEN STEEL POST.

<p>Sketch of Monument, Accessories and General Area</p>	<div style="border: 1px solid black; padding: 5px; text-align: center;"> <p>REGISTERED PROFESSIONAL LAND SURVEYOR</p> <p><i>Lance Clark King</i></p> <p>OREGON MAY 10, 2011 LANCE CLARK KING 61420</p> </div> <p>RENEWS: 6/30/2015</p> <p>Agency: CK3, LLC 945 W. ORCHARD HERMISTON OREGON 97838 OFFICE: 541-567-2345 FAX: 541-567-2305 WEB: CK3LLC.NET Field Book# 0-289</p> <p style="text-align: center;">COUNTY SURVEYOR RECORDING INFO</p> <p>Received <i>Jay Tohart</i></p> <p>Filed <u>6/12/2015</u></p> <p>Survey No. <u>15-050-C</u></p> <p>Drawing No. <u>C-853</u></p> <p>Index No. <u>G-21</u></p>
--	---