

# CORNER RESTORATION FORM

Township 3N Range 30E Section 16,15,21&22 County UMATILLA

State OREGON Date 3-12-2015 Number N-13

Corner Designation : SECTION 16, 15, 21 & 22


- Condition Report Only
- Not Found
- Renewed
- Surveyed In
- Referenced

Previous Renewals ORIGINAL SOURCE OF CORNER

UNDER GLO CONTRACT #95 BY W. CAMPBELL DATED
SEPTEMBER 19, 1860 SET POST
Accessories Found:
NONE

### MONUMENT DETAIL

Found  Set



BASIS OF BEARINGS, NAD 83/91 OREGON STATE PLANE COORDINATES NORTH ZONE:

NORTHING: 756845.738  
EASTING: 8570373.383

#### Monument & Accessories Set (Procedure and Description)

- SET 2 1/2" BRASS CAP ON 1 1/4"x30" PIPE 2' BELOW FIELD GRADE.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE, N1°50'E 249.07', NEAR POWER POLE TO SOUTH.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE, S7°16'E 114.26', BEARING OBJECT SIGN ON POWER POLE.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE, S30°12'W 100.18', BEARING OBJECT SIGN ON FENCE POST IN FENCE LINE.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE, S85°00'W 206.43', IN FENCE LINE.

#### Sketch of Monument, Accessories and General Area

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

**OREGON**  
**MAY 10, 2011**  
**LANCE CLARK KING**  
**61420**

RENEWS: 6/30/2015

Agency:

CK3, LLC  
 945 W. ORCHARD  
 HERMISTON OREGON 97838  
 OFFICE: 541-567-2345  
 FAX: 541-567-2305  
 WEB: CK3LLC.NET  
 Field Book # 0-289

COUNTY SURVEYOR  
RECORDING INFO

Received

Filed 6/12/2015

Survey No. 15-050-C

Drawing No. C-853

Index No. N-13