

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/2/15

CORNER DESIGNATION: The West One-Quarter Corner of Section 1, Township 3 North, Range 31 East, C-21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1/4
S2 | S1
2015
PLS 54657

MONUMENT SET:

Re-established corner by proportioning record GLO latitude between the Southwest and Northwest Corners of Section 1 and shifting latitude point due West to intersect with North-South field berm. At re-established corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 20" below ground level, stamped as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, buried 20" in the ground, bears North 55° East, 32.8 feet.
- A pink deep-1 magnet, buried 20" in the ground, bears South 52° East, 38.4 feet.
- A blue deep-1 magnet, buried 20" in the ground, bears South 40° West, 36.7 feet.
- An orange deep-1 magnet, buried 20" in the ground, bears North 43° West, 35.9 feet.

Buried bearing object tags with magnets. Set steel fence post with witness post sign 1 foot North of monument.

LOCATION AND COMMENTS: Located in North-South field berm.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 770637.71
E = 8612562.81

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

/3N31C21



RENEWS: 6-30-16

15-052-C