

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/1/15

CORNER DESIGNATION: The Northwest Corner of Section 10, Township 3 North, Range 31 East, E-13.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instructions for corner to sections 3, 4, 9 & 10. Corner re-established and remonumented by Dave Krumbein, at a fence line intersection, in Survey M-108-B, dated 1976. Krumbein monumented with a brass cap monument..

MONUMENT AND ACCESSORIES FOUND: Found a 2 ½" brass cap monument 6 " West of a railroad tie marker post in a North-South field berm. Top of monument is 6" below ground.

MONUMENT MARKING DETAIL:

T3N R31E
S4|S3
S9|S10
PLS 933

NEW ACCESSORIES:

From found brass cap, 6" below ground level, stamped as shown in "Monument Marking Detail".

A silver deep-1 magnet buried 20" in the ground, bears North 48° East, 30.3 feet.

A pink deep-1 magnet, buried 20" in the ground, bears South 49° East, 31.3 feet.

A blue deep-1 magnet, buried 20" in the ground, bears South 30° West, 30.0 feet.

An orange deep-1 magnet buried 20" in the ground, bears North 41° West, 31.1 feet

Buried bearing object tags with magnets. Attached witness sign to railroad tie post.

LOCATION AND COMMENTS: 6" West of railroad tie marker post in North-South field berm.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 767939.26

E = 8602024.83

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

/3N31E13



15-052-C

RENEWS: 6-30-16