

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 3/31/15

CORNER DESIGNATION: The North One-Quarter Corner of Section 10, Township 3 North, Range 31 East, E-15

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner. Corner position was calculated by Dave Krumbein on Survey No. M-108-B, in his subdivision of Section 3. The parallel of latitude offset was not applied to the calculation as was common at the time.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1 S3
4 S10
2015
PLS 54657

MONUMENT SET:

Calculated corner position at straight line mid-point between the Southwest and Southeast corners of Section 3 per Survey No. M-102-B. At reestablished corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, top flush with ground, stamped as shown in "Monument Marking Detail".

From which:

A 5/8" x 24" rebar with a 1 1/4" blue plastic cap stamped "Wells Surveying PLS 54657", 2" above ground level, on South hill slope, bears North 11° East, 43.3 feet.

A 5/8" x 24" rebar with a 1 1/4" blue plastic cap stamped "Wells Surveying PLS 54657", 2" above ground level, on South hill slope, bears North 83° East, 44.3 feet.

A pink deep-1 magnet, buried 20" in the ground, bears South 05° West, 38.5 feet.

A blue deep-1 magnet, buried 20" in the ground, bears South 75° West, 32.1 feet.

Buried bearing object tags with magnets. Attached bearing object tags to all rebar accessories. Set wood post 1.5 feet South of monument with witness sign attached, facing South.

LOCATION AND COMMENTS: At a calculated point, 10' +/- North of Despain Gulch, 4' North of the North bank.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 767976.44

E = 8604668.34

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

/3N31E15



RENEWS: 6-30-16

15-052-C