

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 3/27/15

CORNER DESIGNATION: The Northwest Corner of Section 13, Township 3 North, Range 31 East, J-21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instructions for cor to secs 11, 12, 13 & 14. Corner re-established by John Kimbrell, in 1900 survey recorded in Private Survey Book 1, Page 424 and 425. Kimbrell record states: "I therefore set stake at point for Secs 11-12-13 & 14 as agreed by all parties in interest that they would plant a rock themselves as it is night and no stone handy and we could not do it this evening and am to go to Pendleton in the morning. Note: Kimbrell does not state where the corner was set relative to adjacent corners.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E  
S11|S12  
S14|S13  
2015  
PLS 54657

MONUMENT SET:

Held the projected intersection id field berms South and West and old fence line and berm extending East and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top flush with ground, stamped as shown in "Monument Marking Detail".

From which:

A orange deep-1 magnet buried 20" in the ground, bears North 53° East, 32.4 feet.

A silver deep-1 magnet buried 20" in the ground, bears South 52° East, 30.0 feet.

A pink deep-1 magnet buried 20" in the ground, bears South 39° West, 25.1 feet.

An blue deep-1 magnet buried 20" in the ground, bears North 56° West, 26.1 feet.

Buried bearing object tags with magnets. Set steel fence post with witness sign 1 foot South of corner monument.

LOCATION AND COMMENTS: At the projection of a field berm South and West, and a fence line with berm East. Fence starts 130+/- East of corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 762620.09

E = 8612724.13

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS

/3N31J21



RENEWS: 6-30-16

15-052-C