

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 5/6/15.

CORNER DESIGNATION: The Northwest Corner of Section 17, Township 3 North, Range 31 East, J-5.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instructions for corner to secs 7, 8, 17 & 18.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E  
S7|S8  
S18|S17  
2015  
PLS 54657

MONUMENT SET:

I reestablished this corner by proportioning latitude between the West one-quarter corners of Sections 5 and 17, using the Payne record and shifting due East to the old North-South field berm for departure. At the reestablished corner point in old N-S field berm, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground level marked as shown in "Monument Marking Detail".

From which:

A silver deep-1 magnet, buried 20" in the ground, bears North 58° East, 30.5 feet.

A pink deep-1 magnet, buried 20" in the ground, bears South 34° East, 30.0 feet.

A blue deep-1 magnet, buried 20" in the ground, bears South 52° West, 28.8 feet.

A 5/8" x 24" rebar with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54657", 2" above ground level, at the Southeast corner of a metal angle iron post for a Bird Guzzler, bears North 01° West, 38.3 feet.

Buried bearing object tags with magnets. Wired bearing object tag to rebar, nailed witness sign to South side of Bird Guzzler Roof above rebar.

LOCATION AND COMMENTS: Corner located in CRP field in an old North-South field berm.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 762597.00

E = 8591553.19

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

/3N31J5



RENEWS: 6-30-16

15-052-C