

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/07/06

CORNER DESIGNATION: 3N31, N-25, The Northeast Corner of Section 24.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for corner to secs. 13 & 24, T. 3 N., R. 31 E. and Secs. 18 & 19, T. 3 N., R. 32 E. In undated Survey No. Q-521-C, (1950's?) Hayes recovers evidence of this corner and sets a 6 x 8 x 12 stone.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N
R31E | R32E
S13|S18
S24|S19
2006
PLS 1106

MONUMENT SET:

Established corner position 1321.1 feet North of the recovered 1 inch iron pipe established for the North 1/16th corner common to Sections 24 and 19, per Hayes Survey No. Q-521-C (undated). For alignment North of the 1 inch iron pipe, held the record calculated angle of 113°36'14" to the left, when occupying the 1 inch iron pipe and back sighting the recovered fence corner near the center 1/4 corner of Section 19, T3N., R32E., W.M. The 6 x 8 x 12 inch stone reported on Survey No. Q-521-C was not recovered. We made an extensive search for the monuments reported for Section 19 on Survey No. Q-521-C and found only the 1 inch pipe for the N 1/16th corner common to Section 24 & 19, the old fence corner near the Center 1/4 of Section 19 and an uprooted 1 inch pipe near the South 1/16th corner common to Section 13 and 18. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 12" below gravel road surface. Monument marked as shown in monument marking detail.

From which:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" in fence line bears North 37 1/2° East, 31.5 feet. Set steel fence post with witness sign near rebar. A blue Deep-1 magnet buried 22" below ground level bears South 41 1/2° East, 42.9 feet. A purple Deep-1 magnet buried 22" below ground level bears South 55 1/2° West, 34.2 feet. An orange Deep-1 magnet buried 22" below ground level bears North 33° West, 36.5 feet. Attached bearing object sign to rebar accessory and buried bearing object signs with magnets.

LOCATION AND COMMENTS: Corner is located 3 feet South of the South edge of Howdysheil Road. Corner is 8 feet West of a crooked field berm running North-South.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 757351.48
E = 8618082.34


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/3N31N25

Surveyor's Seal



William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

01-11-2-0