

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 03/14/06

CORNER DESIGNATION: 3N31, P-1, The West One-Quarter Corner of Section 19.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by David P. Thompson, under Contract No. 81, dated July 8, 1959. Record states: Set pot for 1/4 Sec. corner and build mound of earth with pits, trench &c., as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T3N  
R30E R31E  
 $\frac{1}{4}$   
S24| S19  
2006  
PLS 1106

**MONUMENT SET:**

Reestablished corner position by single proportionate measure between the recovered or reestablished Southwest and Northwest corners of Section 19. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 16" below ground level in a CRP field. A UECA power pole line runs North and South through corner. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 24" below ground bears North 41° East, 31.7 feet.
  - A blue Deep-1 magnet buried 24" below ground bears South 34° East, 34.7 feet.
  - A purple Deep-1 magnet buried 24" below ground bears South 34° West, 32.1 feet.
  - A orange Deep-1 magnet buried 24" below ground bears North 44° West, 34.4 feet.
- Buried bearing object signs with magnets. Set steel fence post with witness sign attached 1' North of monument.

LOCATION AND COMMENTS: Corner is located in a CRP field with a UECA power pole line running North-South through the corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 754596.02  
E = 8586237.49

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/3N31P1

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-08*