

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/20/06

CORNER DESIGNATION: 3N31, P-9, The West One-Quarter Corner of Section 21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1
4
S20 | S21
2006
PLS 1106

MONUMENT SET:

Held intersection of field lines North-South and East-West as best remaining evidence of corner position, At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

A silver Deep-1 magnet buried 22" below ground level bears North 29° East, 39.4 feet
A blue Deep-1 magnet buried 22" below ground level bears South 40° East, 35.7 feet.
A purple Deep-1 magnet buried 22" below ground level bears South 57 1/2° West, 35.8 feet.
An orange Deep-1 magnet buried 22" below ground level bears North 38 1/2° West, 38.3 feet.
Buried bearing object signs with all magnets. Set steel fence post with witness sign 1 foot North of monument.

LOCATION AND COMMENTS: Corner is located at the intersection of field lines extending North, South, East, and West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 754684.48
E = 8596943.25

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31P9

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08