

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/04/06

CORNER DESIGNATION: 3N31, R-13, The Northwest Corner of Section 27.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for corner to sections 21, 22, 27 & 28.

MONUMENT AND ACCESSORIES FOUND: None. Held the intersection of the centerline of Barnhart Road North and South and a field berm extending East as best remaining evidence of original corner position.

MONUMENT MARKING DETAIL:

T3N R31E
S21|S22
S28|S27
2006
PLS 1106

MONUMENT SET:

At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 12" below gravel road surface. Monument marked as shown in monument marking detail.
From which:
A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 39° East, 25.8 feet.
A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 14° East, 47.5 feet.
A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 22 1/2° West, 48.6 feet.
The center at ground level of a 4 1/2" diameter steel tube post bears North 85° West, 16.6 feet.
Attached witness sign to this tube post.
Attached bearing object signs to all iron rebar accessories.

LOCATION AND COMMENTS: Corner is located at the intersection of the centerline of Barnhart Road North and South and a field berm East. There is a indefinite field line extending West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
N = 752023.54
E = 8602271.79

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31R13

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08