

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/25/06

CORNER DESIGNATION: 3N31, R-7, The South One-Quarter Corner of Section 20.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1 S20
4 S29
2006
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the re-established Southwest and Southeast corners of Section 20. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 53° East, 44.1 feet.
 - A blue Deep-1 magnet buried 22" below ground level bears South 36° East, 45.6 feet.
 - A purple Deep-1 magnet buried 22" below ground level bears South 32 1/2° West, 37.2 feet.
 - An orange Deep-1 magnet buried 22" below ground level bears North 36° West, 39.8 feet.
- Buried bearing object signs with magnets.

LOCATION AND COMMENTS: Corner is located in an actively farmed field. A house bears Northeast 300'+-.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 751984.47
E = 8594357.11

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31R7

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08