

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/20/06

CORNER DESIGNATION: 3N31, R-9, The Southwest Corner of Section 21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D. S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for corner to Secs. 20 & 21, 28 & 29.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
S20|S21
S29|S28
2006
PLS 1106

MONUMENT SET:

Held North-South field line for departure and proportioned latitude between the reestablished East One-Quarter corners of Sections 20 and 29. At reestablished corner position, set a 2 3/8 " brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 24" below ground level bears North 37 1/2° East, 33.6 feet.
 - A blue Deep-1 magnet buried 24" below ground level bears South 27 1/2° East, 38.0 feet.
 - A purple Deep-1 magnet buried 24" below ground level bears South 45 1/2° West, 39.9 feet.
 - An orange Deep-1 magnet buried 24" below ground level bears North 40° West, 40.2 feet.
- Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located in a North-South field between farmed fields.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 752025.89
E = 8596995.76

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31R9

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08