

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/13/06

CORNER DESIGNATION: 3N31, V-11, The South One-Quarter Corner of Section 28.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally set by D. S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1 S28
4 S33
2006
PLS 1106

MONUMENT SET:

Re-established corner on line between the reestablished Southwest and Southeast corners of Section 28, holding the North-South field line through the corner point for departure. At reestablished corner point, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 57 1/2° East, 29.4 feet.
 - A blue Deep-1 magnet buried 22" below ground level bears South 33° East, 37.8 feet.
 - A purple Deep-1 magnet buried 22" below ground level bears South 39° West, 35.5 feet.
 - An orange Deep-1 magnet buried 22" below ground level bears North 37° West, 32.8 feet.
- Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located in North-South field line.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 746710.67
E = 8599717.32

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31V11

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08