

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/13/06

CORNER DESIGNATION: 3N31, V-15, The South One-Quarter Corner of Section 27.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally set by D. S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E  
1 S27  
4 S34  
2006  
PLS 1106

MONUMENT SET:

Reestablished corner position by holding east-west pole and fence line for latitude and record proportioned departure between reestablished corners at the Southwest corner of Section 27 and the Southeast corner of Section 25. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with top 2" above ground level and surrounded with mound of stones. Monument marked as shown in monument marking detail.

From which:

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 05° East, 26.5 feet.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 65 1/2° East, 30.7 feet.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 09 1/2° West, 22.4 feet.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 49 1/2° West, 32.5 feet.

Attached bearing object signs to all rebar accessories. Nailed witness post sign to power pole 3' West of monument.

LOCATION AND COMMENTS: Corner is located 3 feet East of a power pole in unfarmed field corner with power lines extending North and West. A farmed field line extends East approximately 50 feet East of monument. There is remains of fence wire in the corner area.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 746745.70  
E = 8604993.86


FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31V15



*William R. Wells*



*renews 6-30-08*

*2-11-08*