

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/20/06

CORNER DESIGNATION: 3N31, V-9, The Southwest Corner of Section 28.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D. S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for corner to Secs. 28 & 29, 32 & 33.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
S29|S28
S32|S33
2006
PLS 1106

MONUMENT SET:

Reestablished corner position by calculating record proportionate latitude between the reestablished East one-quarter corners of Sections 29 and 32. For departure, I calculated record proportional departure between the reestablished Southwest corner of Section 29 and the North-South field line running through the South One-Quarter corner of Section 28. At reestablished corner position, set a 2 3/8 " brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 24" below ground level bears North 62 1/2° East, 38.8 feet.
 - A blue Deep-1 magnet buried 24" below ground level bears South 21 1/2° East, 43.8 feet.
 - A purple Deep-1 magnet buried 24" below ground level bears South 58° West, 44.5 feet.
 - An orange Deep-1 magnet buried 24" below ground level bears North 31 1/2° West, 51.1 feet.
- Set steel fence post with witness sign attached 1 foot North of monument. Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located in a actively farmed field. There are no nearby features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 746707.83
E = 8597089.67


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31V9



William R. Wells



renews 6-30-08